



**Chatham County Environmental Quality Headquarters Project: Addendum #3**

**DATE: May 9, 2014**

Hobbs Architects, PA  
480 Hillsboro Street, Suite 400  
Pittsboro, North Carolina 27312

**ADDENDUM #3:**

TO: All bidders of record, which have received plans and specifications for the project referred to above.

This Addendum No. 3 forms a part of the Contract Documents and modifies the original Drawings and Specifications dated April 18, 2014 as noted below. Acknowledge receipt of this addendum in the space provided on the Bid Form. Failure to do so may subject bidder to disqualification.

This addendum consists of one (1) 8 ½ x11" pages of written information.

**Specifications:**

**1. Section 23 81 26 - Split-System Air-Conditioners**

Section 2.3A: Replace with the following:

A. Interface Requirements for HVAC Instrumentation and Control System:

1. Interface relay for scheduled operation.
2. Interface relay to provide indication of fault at the central workstation and diagnostic code storage.
3. Provide BACnet compatible interface for central HVAC control workstation for the following:
  - a. Adjusting set points.
  - b. Monitoring supply fan start, stop, and operation.
  - c. Monitoring occupied and unoccupied operations.
  - d. Monitoring constant and variable motor loads.
  - e. Monitoring cooling load.

**END OF ADDENDUM #3**