ADDRESS

14 N. Boylan Avenue, Raleigh NC 27603

TEL 919.828.0577

WEB

www.smithgardnerinc.com

July 14, 2016

ADDENDUM NO. 2 TO THE CONTRACT DOCUMENTS FOR CHATHAM COUNTY SOLID WASTE AND RECYCLING RECYCLING STATION

BID ISSUE DATE: JUNE 2016

To All Plan Holders:

The following revisions, additions and clarifications are hereby made part of the Contract Documents for the above-referenced project and shall be taken into account in the preparation of all Bids and the execution of all work. Bidders shall acknowledge receipt of the Addendum in the appropriate space on the Proposal Form. Failure to do so may result in your Bid being considered non-responsive.

I. SPECIFICATIONS

A. Proposal:

<u>DELETE</u> Pages P-5 through P-8 of the Bid" and <u>REPLACE</u> with the attached Pages P-5 through P-8.

B. <u>Section 01025 (Measurement and Payment):</u>

<u>DELETE</u> Section 01025 (Measurement and Payment) and <u>REPLACE</u> with the attached Section 01025 (Measurement and Payment).

II. QUESTIONS

AD2-1 I do not see any notations about HSS or steel uprights in the fabric wall

with the 40' opening, is this just a fabric wall with no supports?

Answer: The opening in the rear of the structure will need to be designed to

withstand the design wind speed (i.e., 90 mph). All supports (vertical and horizontal members) for the fabric wall and opening are to be

provided by the building supplier.

Chatham County Solid Waste & Recycling – Recycling Station

Addendum No. 2 - July 14, 2016

Page 2 of 4

AD2-2 What is the height of this opening from grade?

Answer: As shown in Detail 7/D2 on Sheet 8, the finished grade elevation of the

slab is EL 501, the top of wall elevation is 505, and the opening is 10 feet above the top of the wall (EL 515). Therefore, the top of the

opening is 14 feet above the finished grade of the slab.

AD2-3 Please verify the live load requirements for the fabric roof structure.

Answer: The roof live load requirement (found on drawing ST2) is here by

changed to 5 PSF, based on the IBC Table 1607.1 in reference to fabric construction supported by lightweight rigid skeleton structure. The

change will be made on the construction issue drawings.

AD2-4 The detail on page D1 for the fence gate shows a swing gate D2 shows

a slide gate and the specs call out a cantilever gate can you clarify?

Answer: The fence will have a slide gate.

AD2-5 T The center to center bolt measurement does not have to be exactly as

the Clearspan?

Answer: No. The building trusses are to bear to the new foundation and shall

avoid the concrete bin blocks as shown in detail 2/ST3. The exact location of center of bolts is up to the building supplier provided that it

meets this criteria.

AD2-6 The on center truss spacing does not have to be exactly as the as

shown on the drawings?

Answer: No.

AD2-7 The height of the building does not have to be exactly as the shown on

the drawings?

Answer: No; however the building shall provide a minimum clearance of 24' for

the center 28 feet

AD2-8 Is this FR (fire rated) material or Non-FR?

Answer: Yes. The material should be fire rated.

AD2-9 What is the wind mph design load for this shelter? Is it a 90 mph wind

load?

Answer: Yes, as shown on sheet ST2.

Chatham County Solid Waste & Recycling – Recycling Station

Addendum No. 2 - July 14, 2016

Page 3 of 4

AD2-10 Is the shelter designed using the current 2012 IBC or 2009 IBC? Or,

what North Carolina Code is being used to calculate shelter

requirements?

Answer: The Building must meet the requirements of the 2012 North Carolina

Building Code.

AD2-11 Design wind speed under 2009 is 90-C, under 2012 it is 105-C?

Answer: The 2012 North Carolina Building Code is based on the 2009 IBC.

Please reference the NC Building Code. The design wind speed per the

NCBC is 90 mph.

AD2-12 This is a Commercial Building but is it considered Category 1 or 2?

Answer: For the purposed of design, we are considering this building to be

Occupancy Category 1.

AD2-13 Are the post-production hot dipped galvanized trusses required?

Answer: Trusses should be galvanized steel or aluminum.

AD2-14 Are Stamped Engineered Shop Drawings required for the Shelter

Answer Yes. Stamped Engineering Shop Drawings will be required.

AD2-15 Where is the structural Steel requirement and header requirement for

the 40' wide by 14' tall opening in the end wall of the building?

Answer: Please refer to the answer to ADS-1

AD2-16 Is the snow load requirement 15lbs or 20lbs?

Answer: The snow load requirement is 15 psf.

AD2-17 Any seismic requirments and if so what Zone and soils classification>

Answer: The seismic requirements of the 2012 North Carolina Building Code

must be considered. Bidders should assume seismic soil classification

D.

AD2-18 Will the rear canvas wall be constructed flush with the New Retaining

Wall at the rear of the building (rest on top) or will it be constructed to

be in front of the New Retaining Wall?

Chatham County Solid Waste & Recycling – Recycling Station

Addendum No. 2 – July 14, 2016

Page 4 of 4

Answer: The rear canvas wall will be constructed flush with the New

RetainingWall. The length of the Concrete Retaining Wall at the rear of the building will be reduced from 68' to accommodate the end trusses.

AD2-19 This is calling for a 9.5C and 25C design mix. This requires the asphalt

plant to order special blend of asphalt liquid.

Answer: The design mix can be changed to a type B mix.

AD2-20 Detail 3 on Drawing EL3 is "Typical" and shows 4 conduits. Is it safe to

assume we only need to install 1 conduit?

Answer: Yes, you only need to install one conduit.

AD2-21 Does Detail 3 on Drawing EL3 apply to the light pole also? or is direct

burial ok?

Answer: All buried lines will be in conduit, with soil compacted around the

conduit as shown on Detail 3 Drawing EL3


AD2-22 What type of enclosures are required in the structure? NEMA 4 or

NEMA 4X?

Answer: The enclosures will be Nema 4.

END OF ADDENDUM

Submitted by, **SMITH GARDNER, INC.**



W. Michael Brinchek, P.E. Project Manager mike@smithgardnerinc.com

Attachment: Proposal Pages P-5 through P-8

Specification Section 01025

A. <u>Base Bid Schedule:</u>

Pay Item Number	Description	Spec. Reference	Estimated Quantity ¹	Units	Unit Cost	Extended Cost
1.0	Demolition					
1.1	Gravel Removal		1	LS	Lump Sum	
1.2	Concrete Pad Removal (Base of Conc. Block Wall)		1	LS	Lump Sum	
1.3	Block Wall Removal		1	LS	Lump Sum	
1.4	Barricade Removal		1	LS	Lump Sum	
2.0	Site Preparation	02110	6,400	SY		
3.0	Erosion and Sedimentation Control	02270				
3.1	Silt Fence	02270	395	LF		
3.2	Stone Filter Fence	02270	40	LF		
3.3	Temporary Gravel Construction Entrance/Exit	02270	2	EA		
3.4	Sediment Basin	02270	1	EA		
3.5	Rip Rap Lined Channel		120	LF		
3.6	Rip Rap Outlet Protection		3	EA		
4.0	Earthwork					
4.1	Excavation	02222	1	LS	Lump Sum	
4.2	Embankment	02223	1	LS	Lump Sum	
4.3	Undercut and Backfill Unsuitable Materials	02222	1	LS	Lump Sum	
5.0	Stormwater Management					
5.1	Reinforced Concrete Pipe Culvert	02608	70	LF		
5.2	Catch Basins	02608	2	EA		
6.0	Pavement	02500				

Pay Item Number	Description	Spec. Reference	Estimated Quantity ¹	Units	Unit Cost	Extended Cost
6.1	6-Inch-Thick Aggregate Surfacing	02500	340	SY		
6.2	12-Inch-Thick Aggregate Surfacing	02500	1,000	SY		
6.3	Asphalt Surfacing	02500	780	SY		
7.0	Waterline	02616	270	LF		
8.0	Chain Link Fencing	02820				
8.1	Chain Link Fence – New	02820	170	LF		
8.2	Chain Link Fence – Panel Replacement	02820	4	EA		
8.3	Chain Link Gates	02820	2	EA		
9.0	Revegetation	02930				
9.1	Revegetation (Seeding)	02930	21,900	SF		
9.2	Revegetation (Sodding)	02930	5,500	SF		
10.0	Concrete Work			LS	Lump Sum	
10.1	Reinforced Concrete Retaining Wall	Drawings	1	LS	Lump Sum	
10.2	Reinforced Concrete Side Wall	Drawings	1	LS	Lump Sum	
10.3	Reinforced Concrete Slab (Tipping Floor)	Drawings	1	LS	Lump Sum	
10.4	Concrete Surfacing (Loading Area)	Drawings	1	LS	Lump Sum	
11.0	Fabric Structure		1	LS	Lump Sum	
12.0	Concrete Block Wall (2x2x6 Bin Block)		1	LS	Lump Sum	
13.0	Yard Hydrant		1	EA		
14.0	Bollard		8	EA		
15.0	Electrical Work and Lighting– Base Bid	Drawings	1	LS	Lump Sum	
16.0	Bonds, Mobilization, & Insurance: (Max. = 4% of Total Bid Price)			LS	Lump Sum	

The TOTAL BASE BID PRICE for the pay items listed above is as follows:			
(In Words)	Dollars and	Cents.	
(In Numbers) (\$)			

Notes:


1. Engineer's estimated quantities are based on in-place quantities. Areas and lengths are based on horizontally projected areas and lengths. No adjustments have been made for stripping topsoil, slopes, uneven contours, compaction factors, etc.

NOTE: PROPOSAL SIGNATURE REQUIRED ON PAGE P-15. ALL PROPOSALS MUST BE PROPERLY EXECUTED TO BE CONSIDERED A VALID BID.

B. <u>Miscellaneous Additions and Deductions:</u>

The Bidder agrees that the Owner has the full unconditional right to select any combination of additions or deductions and adjust the total Contract price accordingly. Variations from estimated quantities shall be in accordance with the General Conditions. For additions or deductions as described by the Engineer, the following unit prices bid under the Base Bid shall apply:

Misc. Item Number	Description	Spec. Reference	Units	Unit Price
1	Deduct Item 10.2 - Reinforced Concrete Slab (Tipping Floor)	Drawings	LS	
2.1	Add Electrical – Option 1 to Item 15 – Electrical Base Bid	Drawings	LS	
2.2	Add Electrical – Option 2 to Item 15 – Electrical Base Bid	Drawings	LS	



SECTION 01025

MEASUREMENT AND PAYMENT

A. General

This Section includes the units and methods of measurement and the basis of payment for work done under this Contract. The work required for each item shall be as required and/or reasonably implied by the Contract Documents to complete the work. Note that all measurement work shall be subject to verification (surveyed or otherwise) by the Owner.

B. Measurement and Payment

1. <u>Demolition:</u>

All work required for <u>Demolition</u> which is not otherwise covered under related sections of these Specifications, shall be included for payment in the Contractor's Lump Sum and Unit Price Bid for the following items:

- a. <u>Gravel Removal</u>, which includes the removal and stockpiling of gravel surfaces, shall be paid for on the basis of the Unit Price Bid for this work, per cubic yard stockpiled. Measurement of this quantity shall be made by the Contractor's Surveyor.
- b. <u>Block Wall Removal</u>, which includes related earthwork and storage of blocks, shall be included for payment in the Contractor's Lump Sum Price for this work, wherein no measurement will be made.
- c. <u>Barricade Removal</u>, which includes related earthwork and storage of barricades, shall be included for payment in the Contractor's Lump Sum Price for this work, wherein no measurement will be made.

2. <u>Section 02110: Site Preparation:</u>

All work required for <u>Site Preparation</u> shall be included for payment in the Contractor's Unit Price Bid for this work, per square yard prepared. Measurement of this area shall be made by the Contractor's surveyor based on the horizontal projected area. No adjustments will be made in the area for slope or uneven contours.

3. <u>Section 02270: Erosion and Sedimentation Control:</u>

All work required for <u>Erosion and Sedimentation Control</u>, which is not otherwise covered under related sections of these Specifications, shall be included for payment in the Contractor's Lump Sum and Unit Price Bid for the following items:

a. <u>Silt Fence</u>, which includes related earthwork and materials, shall be paid on the basis of the Unit Price Bid for this work, per linear foot in-place. Measurement of silt fence shall be made by the Contractor's surveyor based on the horizontal

- projected length. No adjustments will be made in the length for slopes, uneven contours, overlaps, seams, repairs, or wasted material.
- b. <u>Stone Filter Fence</u>, which includes related earthwork and materials (including fencing, stone, etc.), shall be paid on the basis of the Unit Price Bid for this work, per linear foot in-place.
- c. <u>Temporary Gravel Construction Entrance/Exit</u>, which includes related earthwork and materials, shall be paid on the basis of the Unit Price Bid for this work, per each entrance/exit in-place.
- d. <u>Sedimentation Basins</u>, which includes related earthwork and materials (including riser/barrel structure, baffles, etc.) shall be paid on the basis of the Contractor's Lump Sum Price for this work, wherein no measurement will be made.

4. Section 02222: Excavation:

All work required for <u>Excavation</u> shall be included for payment in the Contractor's Unit Price Bid for this work, per cubic yard excavated. Measurement of this quantity shall be made by the Contractor's surveyor.

5. <u>Section 02223: Embankment:</u>

All work required for Embankment shall be included for payment in the Contractor's Unit Price Bid for this work, per cubic yard in-place. Measurement of this quantity shall be made by the Contractor's surveyor.

6. Section 02500: Roadway Work:

All work required for Roadway Work shall be included for payment in the following items:

- a. <u>Aggregate Surfacing</u>, which includes related earthwork and materials (including Type GT-S geotextile and ABC), shall be paid on the basis of the Unit Price Bid for this work, per square yard in-place. Measurement of this area shall be made by the Contractor's surveyor based on the horizontal projected area. No adjustments will be made in the length for slopes, uneven contours, repairs, or wasted material.
- b. <u>Asphalt Surfacing</u>, which includes related earthwork and materials (including Type GT-S geotextile, ABC, and asphalt), shall be paid on the basis of the Unit Price Bid for this work, per square yard in-place. Measurement of this area shall be made by the Contractor's surveyor based on the horizontal projected area. No adjustments will be made in the length for slopes, uneven contours, repairs, or wasted material.
- c. <u>Asphalt-Gravel Transition</u>, which includes related earthwork and materials (including Type GT-S geotextile, ABC, concrete, and asphalt), shall be paid on the basis of the Unit Price Bid for this work, per square yard in-place. Measurement of this area shall be made by the Contractor's surveyor based on the horizontal

projected area. No adjustments will be made in the length for slopes, uneven contours, repairs, or wasted material.

7. Section 02608: Precast Concrete Structures:

All work required for <u>Precast Concrete Structures</u>, which is not otherwise covered under related sections of these Specifications, shall be included for payment in the following items:

- a. All work required for <u>Precast Concrete Pipe</u>, which includes related earthwork and materials, shall be included for payment in the Contractor's Unit Price Bid for this work, per linear foot in-place.
- b. All work required for <u>Precast Concrete Catch Basins</u>, which includes related earthwork and materials, shall be included for payment in the Contractor's Unit Price Bid for this work, per each drop inlet in-place.

8. <u>Section 02616: PVC Pipe:</u>

All work required for <u>PVC Pipe</u>, which includes all related fittings and appurtenances, shall be included for payment in the Contractor's Unit Price Bid for this work, per linear foot of each size pipe in-place.

9. Section 02820: Chain Link Fence and Gates:

All work required for <u>Chain Link Fence and Gates</u> shall be included for payment in the Contractor's Unit Price Bid for the following items:

- a. <u>Chain Link Fence</u>, per linear foot installed.
- b. <u>Gates</u>, per each gate installed.

10. <u>Section 02930: Revegetation:</u>

All work required for <u>Revegetation</u> which is not otherwise covered under related sections of these Specifications, shall be included for payment in the Contractor's Lump Sum and Unit Price Bid for the following items:

- a. Revegetation (Seeding) shall be included for payment in the Contractor's Unit Price Bid for this work, per square feet in-place. Measurement of this area shall be made by the Contractor's surveyor based on the horizontal projected area. No adjustments will be made in the area for slopes, uneven contours, repairs, or wasted material.
- b. Revegetation (Sodding) shall be included for payment in the Contractor's Unit Price Bid for this work, per square feet in-place. Measurement of this area shall be made by the Contractor's surveyor based on the horizontal projected area. No adjustments will be made in the area for slopes, uneven contours, repairs, or wasted material.

11. Concrete Work:

All work required for <u>Concrete Work</u> shall be considered incidental to the other pay items in this contract and no separate measurement or payment will be made, except for the following items:

- a. Reinforced Concrete Retaining Wall, which includes all related earthwork and materials (including steel, formwork, concrete, wall and footing drains, dock bumpers, railing, etc.), shall be included for payment in the Contractor's Lump Sum Price for this work, wherein no measurement will be made.
- b. Reinforced Concrete Side Wall, which includes all related earthwork and materials (including steel, formwork, concrete, wall and footing drains, etc.), shall be included for payment in the Contractor's Lump Sum Price for this work, wherein no measurement will be made.
- c. Reinforced Concrete Slab (Tipping Floor), which includes all related earthwork and materials (including Type GT-S geotextile, ABC, steel, formwork, concrete, etc.), shall be included for payment in the Contractor's Lump Sum Price for this work, wherein no measurement will be made.
- c. <u>Concrete Surfacing (Loading Area)</u>, which includes all related earthwork and materials, (including Type GT-S geotextile, ABC, steel, formwork, concrete, etc.) shall be included for payment in the Contractor's Lump Sum Price for this work, wherein no measurement will be made.

12. Fabric Structure:

All work required for <u>Fabric Structure</u>, which includes engineering design, fabrication and installation, shall be included for payment in the Contractor's Lump Sum Price for this work, wherein no measurement will be made.

13. Concrete Block Wall (2x2x6 Bin Block)

All work required for <u>Concrete Block Wall (2x2x6 Bin Block</u>, which includes hauling and installation (bin block materials will be purchased by County,) shall be included for payment in the Contractor's Lump Sum Price for this work, wherein no measurement will be made.

14. Yard Hydrant

All work required for Yard Hydrant shall be included for payment in the Contractor's Unit Price Bid, per unit installed.

15. Bollards:

All work required for <u>Bollards</u>, which includes related earthwork and materials shall be included for payment in the Contractor's Unit Price Bid for this work, per each bollard inplace.

16. Electrical Work and Lighting – Base Bid:

All work required for <u>Electrical Work and Lighting – Base Bid</u>, which includes all related work and materials, shall be included for payment in the Contractor's Lump Sum Price for this work, wherein no measurement will be made.

17. <u>Utility Connections/Relocations:</u>

All work required for <u>Utility Connections/Relocations</u>, which includes all related earthwork and materials to make connections, relocations, and installations for utilities as shown or indicated on the Contract Drawings (including water, fire, sewer, and electrical conduits), shall be considered incidental to the other pay items in this contract and no separate measurement or payment will be made.

18. Quality Control Testing:

All work required for <u>Quality Control Testing</u> shall be considered incidental to the other pay items in this contract and no separate measurement or payment will be made


19. Bonds, Mobilization, and Insurance:

This work shall consist of securing the appropriate bonds and insurance policies for the project, performance of preparatory construction operations, and performance of project closeout activities including the movement of personnel and equipment to and from the project site, safety equipment, and other facilities to begin work on a substantial phase of the Contract. All work required for Bonds, Mobilization, and Insurance shall be included for payment in the Contractor's Lump Sum Price for this work, wherein no measurement will be made. The amount of this item shall be limited to a maximum of four percent of the total Bid price. At least twenty (20) percent of this item must be allocated for demobilization at the end of the project.

C. Submittals

Before completion of the first pay application, the Contractor shall prepare and submit copies of his proposed pay application to the Engineer for review.

END OF SECTION



This page intentionally left blank.

Recycling Station General Specifications July 2016



Certificate Of Completion

Envelope Id: 1D9112C44B40406E94DAD1292D927E5A

Subject: Please DocuSign: CC Addendum No. 2 07-14-2016.pdf

Source Envelope:

Document Pages: 14 Signatures: 1 Envelope Originator: Certificate Pages: 4 Initials: 0 Smith Gardner, Inc. AutoNav: Enabled 14 N. Boylan Ave Envelopeld Stamping: Enabled Raleigh, NC 27603

Time Zone: (UTC-05:00) Eastern Time (US & Canada)

docusign@smithgardnerinc.com IP Address: 24.106.183.110

Status: Completed

Record Tracking

Status: Original Holder: Smith Gardner. Inc. Location: DocuSign

July 14, 2016 | 14:49 docusign@smithgardnerinc.com

Signer Events

Mike Brinchek mike@smithgardnerinc.com Senior Project Manager

Blahhhhhhhh

Security Level: Email, Account Authentication

(None)

Electronic Record and Signature Disclosure:

Accepted: July 14, 2016 | 14:52

ID: 8e55f3f8-36a3-444a-b3dd-63a263d43954

Signature Timestamp

> Sent: July 14, 2016 | 14:51 Viewed: July 14, 2016 | 14:52 Signed: July 14, 2016 | 14:54

Using IP Address: 70.215.35.153

Signed using mobile

In Person Signer Events	Signature	Timestamp
Editor Delivery Events	Status	Timestamp
Agent Delivery Events	Status	Timestamp
Intermediary Delivery Events	Status	Timestamp
Certified Delivery Events	Status	Timestamp
Carbon Copy Events	Status	Timestamp
Notary Events		Timestamp
Envelope Summary Events	Status	Timestamps
Envelope Sent	Hashed/Encrypted	July 14, 2016 14:51

Certified Delivered Security Checked July 14, 2016 | 14:52 Signing Complete Security Checked July 14, 2016 | 14:54 Completed Security Checked July 14, 2016 | 14:54

Electronic Record and Signature Disclosure

ELECTRONIC RECORD AND SIGNATURE DISCLOSURE

From time to time, Smith Gardner, Inc. (we, us or Company) may be required by law to provide to you certain written notices or disclosures. Described below are the terms and conditions for providing to you such notices and disclosures electronically through the DocuSign, Inc. (DocuSign) electronic signing system. Please read the information below carefully and thoroughly, and if you can access this information electronically to your satisfaction and agree to these terms and conditions, please confirm your agreement by clicking the 'I agree' button at the bottom of this document.

Getting paper copies

At any time, you may request from us a paper copy of any record provided or made available electronically to you by us. You will have the ability to download and print documents we send to you through the DocuSign system during and immediately after signing session and, if you elect to create a DocuSign signer account, you may access them for a limited period of time (usually 30 days) after such documents are first sent to you. After such time, if you wish for us to send you paper copies of any such documents from our office to you, you will be charged a \$0.00 per-page fee. You may request delivery of such paper copies from us by following the procedure described below.

Withdrawing your consent

If you decide to receive notices and disclosures from us electronically, you may at any time change your mind and tell us that thereafter you want to receive required notices and disclosures only in paper format. How you must inform us of your decision to receive future notices and disclosure in paper format and withdraw your consent to receive notices and disclosures electronically is described below.

Consequences of changing your mind

If you elect to receive required notices and disclosures only in paper format, it will slow the speed at which we can complete certain steps in transactions with you and delivering services to you because we will need first to send the required notices or disclosures to you in paper format, and then wait until we receive back from you your acknowledgment of your receipt of such paper notices or disclosures. To indicate to us that you are changing your mind, you must withdraw your consent using the DocuSign 'Withdraw Consent' form on the signing page of a DocuSign envelope instead of signing it. This will indicate to us that you have withdrawn your consent to receive required notices and disclosures electronically from us and you will no longer be able to use the DocuSign system to receive required notices and consents electronically from us or to sign electronically documents from us.

All notices and disclosures will be sent to you electronically

Unless you tell us otherwise in accordance with the procedures described herein, we will provide electronically to you through the DocuSign system all required notices, disclosures, authorizations, acknowledgements, and other documents that are required to be provided or made available to you during the course of our relationship with you. To reduce the chance of you inadvertently not receiving any notice or disclosure, we prefer to provide all of the required notices and disclosures to you by the same method and to the same address that you have given us. Thus, you can receive all the disclosures and notices electronically or in paper format through the paper mail delivery system. If you do not agree with this process, please let us know as described below. Please also see the paragraph immediately above that describes the consequences of your electing not to receive delivery of the notices and disclosures

electronically from us.

How to contact Smith Gardner, Inc.:

You may contact us to let us know of your changes as to how we may contact you electronically, to request paper copies of certain information from us, and to withdraw your prior consent to receive notices and disclosures electronically as follows:

To contact us by email send messages to: emily@smithgardnerinc.com

To advise Smith Gardner, Inc. of your new e-mail address

To let us know of a change in your e-mail address where we should send notices and disclosures electronically to you, you must send an email message to us at emily@smithgardnerinc.com and in the body of such request you must state: your previous e-mail address, your new e-mail address. We do not require any other information from you to change your email address.. In addition, you must notify DocuSign, Inc. to arrange for your new email address to be reflected in your DocuSign account by following the process for changing e-mail in the DocuSign system.

To request paper copies from Smith Gardner, Inc.

To request delivery from us of paper copies of the notices and disclosures previously provided by us to you electronically, you must send us an e-mail to emily@smithgardnerinc.com and in the body of such request you must state your e-mail address, full name, US Postal address, and telephone number. We will bill you for any fees at that time, if any.

To withdraw your consent with Smith Gardner, Inc.

To inform us that you no longer want to receive future notices and disclosures in electronic format you may:

i. decline to sign a document from within your DocuSign session, and on the subsequent page, select the check-box indicating you wish to withdraw your consent, or you may; ii. send us an e-mail to emily@smithgardnerinc.com and in the body of such request you must state your e-mail, full name, US Postal Address, and telephone number. We do not need any other information from you to withdraw consent.. The consequences of your withdrawing consent for online documents will be that transactions may take a longer time to process..

Required hardware and software

Operating Systems:	Windows® 2000, Windows® XP, Windows
	Vista®; Mac OS® X
Browsers:	Final release versions of Internet Explorer® 6.0
	or above (Windows only); Mozilla Firefox 2.0
	or above (Windows and Mac); Safari TM 3.0 or
	above (Mac only)
PDF Reader:	Acrobat® or similar software may be required
	to view and print PDF files
Screen Resolution:	800 x 600 minimum
Enabled Security Settings:	Allow per session cookies

^{**} These minimum requirements are subject to change. If these requirements change, you will be asked to re-accept the disclosure. Pre-release (e.g. beta) versions of operating systems and browsers are not supported.

Acknowledging your access and consent to receive materials electronically

To confirm to us that you can access this information electronically, which will be similar to other electronic notices and disclosures that we will provide to you, please verify that you were able to read this electronic disclosure and that you also were able to print on paper or electronically save this page for your future reference and access or that you were able to e-mail this disclosure and consent to an address where you will be able to print on paper or save it for your future reference and access. Further, if you consent to receiving notices and disclosures exclusively in electronic format on the terms and conditions described above, please let us know by clicking the 'I agree' button below.

By checking the 'I agree' box, I confirm that:

- I can access and read this Electronic CONSENT TO ELECTRONIC RECEIPT OF ELECTRONIC RECORD AND SIGNATURE DISCLOSURES document; and
- I can print on paper the disclosure or save or send the disclosure to a place where I can print it, for future reference and access; and
- Until or unless I notify Smith Gardner, Inc. as described above, I consent to receive from exclusively through electronic means all notices, disclosures, authorizations, acknowledgements, and other documents that are required to be provided or made available to me by Smith Gardner, Inc. during the course of my relationship with you.